




ISSUE	APPROVED BY	DATE	AMENDMENT
B	DC.	10/15	AMENDED HEIGHT OF POST, SOIL PLATE BOLT LOCATIONS AND NOTE 6




LAYOUT PLAN



DETAIL PLAN



SECTION A-A



ELEVATION

- NOTES:
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE
 - THE AGREEMENT OF THE MANAGER ROAD STANDARDS AND TRAFFIC SHOULD BE SOUGHT BEFORE MODIFICATIONS ARE MADE TO ANY PART OF THE DESIGN
 - END POST SHALL BE FORMED FROM BMT 4.3 STEEL GRADE HA300 IN ACCORDANCE WITH AS 1594
 - SOIL PLATE, SHELF ANGLE & BEARING PLATE SHALL BE FABRICATED FROM STEEL GRADE 250 IN ACCORDANCE WITH AS 1594
 - BOLTS TO BE SNUG TIGHTENED TO AS4100
 - THE TRAILING TERMINAL IS NOT CRASHWORTHY WHEN IMPACTED FROM THE REVERSE DIRECTION AND THEREFORE CAN ONLY BE USED WHEN THERE IS NO PRACTICAL CHANCE OF BEING IMPACTED BY OPPOSING TRAFFIC
 - WHERE THE FACE OF GUARD FENCE IS ERECTED WITHIN 0 TO 1m BEHIND THE BACK OF KERB, THE MOUNTING HEIGHT SHALL BE MEASURED FROM THE ADJACENT ROAD PAVEMENT SURFACE. HOWEVER THE VERTICAL POSITION OF THE DRILLED HOLE & ANCHOR CABLE ASSEMBLY IN THE END POST SHALL BE MEASURED FROM THE GROUND SURFACE

BOLT SCHEDULE FOR END POST OF TRAILING TERMINAL

ANCHOR PLATE AND BULLNOSE	13 No. SPLICE BOLTS WITH OVERSIZE NUTS
END POST	1 No. M16 METRIC MUSHROOM HEAD POST BOLT WITH M16 NUT 1 WASHER & 1 SPECIAL WASHER
ANCHOR CABLE	2 No M24 NUTS AND CUT WASHERS
SOIL PLATE	2 No M20x40 HEX HEAD BOLT 25 MIN LONG THREAD WITH M20 NUT

M20 X 40 LONG HEX BOLTS WITH NUTS REFER SD3562

SOIL PLATE REFER SD3562

END POST - C-POST

END POST - C-POST

REFERENCES AND NOTES:

SD 3562 TRAILING TERMINAL COMPONENT DETAILS
SD 3661 GUARD FENCE (TYPE B) STEEL POST
VR STANDARD SPECIFICATION 708 STEEL BEAM GUARD FENCE
ROAD DESIGN NOTE 06-08

TECHNICAL SERVICES
MANAGER ROAD STANDARDS & TRAFFIC
60 DENMARK STREET KEW VICTORIA 3101
PHONE (03) 9854 2666



ROAD SAFETY BARRIERS
TRAILING TERMINAL
GENERAL ARRANGEMENT

NOT TO SCALE	APPROVED D.CASSAR	SD NO. 28-11-13 SD 3544	ISSUE B
--------------	----------------------	-------------------------------	------------

VicRoads Drawing No. 720264